

Custom Casework Company
 555 Niles Ave
 Chicago, IL 12345
 555-555-5555

DOOR SIZES 3/4"simple arch frame (Red Oak) with glass panel(s)

Qty	Width	Height	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 6	14 31/32"	41 1/2"	door	cab 07(2) cab 06(2) cab 05(2)

Total square footage is 25.87
 Total Qty is 6

DOOR SIZES 3/4"square frame (Red Oak) with mirror panel(s)

Qty	Width	Height	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 2	22 1/2"	25 1/4"	door	cab 03 cab 02

Total square footage is 7.89
 Total Qty is 2

PLANT-ON SIZES 3/4"compound arch frame (Red Oak) with raised panel(s) (Red Oak)

Qty	Width	Height	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 1	23 15/16"	30 1/2"	plant-on	cab 04
<input type="checkbox"/> 1	11 15/16"	42"	plant-on	cab 07

Total square footage is 8.55
 Total Qty is 2

DRAWER-FRONT SIZES 3/4"slab (horizontal grain)(Red Oak) with no edging

Qty	Width	Height	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 6	22 1/2"	8 19/32"	drawer-front	cab 04(3) cab 01(3)
<input type="checkbox"/> 4	22 1/2"	5"	drawer-front	cab 04 cab 03 cab 02 cab 01

Total square footage is 11.17
 Total Qty is 10

PARTS LIST for DOORS (Stiles)

Material: 3/4" Red Oak

Qty	Width	Length	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 6	2 1/4"	41 1/2"	Left	cab 05 ₍₂₎ cab 06 ₍₂₎ cab 07 ₍₂₎
<input type="checkbox"/> 6	2 1/4"	41 1/2"	Right	cab 05 ₍₂₎ cab 06 ₍₂₎ cab 07 ₍₂₎
<input type="checkbox"/> 2	2 1/4"	25 1/4"	Left	cab 02 cab 03
<input type="checkbox"/> 2	2 1/4"	25 1/4"	Right	cab 02 cab 03

Total length of 2 1/4" width is 599"

Total Qty is 16

PARTS LIST for DOORS (Rails)

Material: 3/4" Red Oak

Qty	Width	Length	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 2	2 1/4"	19"	Top	cab 02 cab 03
<input type="checkbox"/> 2	2 1/4"	19"	Bottom	cab 02 cab 03
<input type="checkbox"/> 6	2 1/4"	11 15/32"	Top	cab 05 ₍₂₎ cab 06 ₍₂₎ cab 07 ₍₂₎
<input type="checkbox"/> 6	2 1/4"	11 15/32"	Bottom	cab 05 ₍₂₎ cab 06 ₍₂₎ cab 07 ₍₂₎

Total length of 2 1/4" width is 213 1/2"

Total Qty is 16

PARTS LIST for DRAWER-FRONTS (Slabs)

Material: 3/4" Red Oak

Qty	Width	Length	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 6	8 19/32"	22 1/2"	Horizontal Grain	cab 01 ₍₃₎ cab 04 ₍₃₎
<input type="checkbox"/> 4	5"	22 1/2"	Horizontal Grain	cab 01 cab 02 cab 03 cab 04

Total square footage is 11.17

Total Qty is 10

PARTS LIST for PLANT-ONS (Panels)

Material: 1/2" Red Oak

Qty	Width	Length	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 1	18 11/16"	22 3/4"	Raised	cab 04
<input type="checkbox"/> 1	6 11/16"	34 1/4"	Raised	cab 07

Custom Casework Company
555 Niles Ave
Chicago, IL 12345
555-555-5555

Total square footage is 4.54

Total Qty is 2

PARTS LIST for PLANT-ONS (Stiles)

Material: 3/4" Red Oak

Qty	Width	Length	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 1	3"	42"	Left	cab 07
<input type="checkbox"/> 1	3"	42"	Right	cab 07
<input type="checkbox"/> 1	3"	30 1/2"	Left	cab 04
<input type="checkbox"/> 1	3"	30 1/2"	Right	cab 04

Total length of 3" width is 145"

Total Qty is 4

PARTS LIST for PLANT-ONS (Rails)

Material: 3/4" Red Oak

Qty	Width	Length	Part Name	Cabinet(pieces per cabinet)
<input type="checkbox"/> 1	6"	18 15/16"	Bottom	cab 04
<input type="checkbox"/> 1	6"	6 15/16"	Bottom	cab 07
<input type="checkbox"/> 1	4"	18 15/16"	Top	cab 04
<input type="checkbox"/> 1	4"	6 15/16"	Top	cab 07

Total length of 6" width is 25 7/8"

Total length of 4" width is 25 7/8"

Total Qty is 4
